

Tel: 416-392-5900 Fax: 416-392-5934

2022-03-03

REQUEST FOR QUOTATION VARIOUS FENCING REPLACEMENT RFQ 01 (2022-01) REV. ADDENDUM #1

This addendum shall be incorporated into, and form part of RFQ 01 (2022-01) REV. and take precedence over all requirements of the previously issued bid documents including plans. This addendum must be signed by the bidder (signing officer) in the appropriate space and must be attached to the Form for submission by the bidder. This Addendum consists of one (1) page.

1. DRAWINGS/SPECIFICATIONS:

The following form part of the RFQ

- a. Barrier Fencing Amur Tiger
- b. Barrier Fencing Cheetah
- c. Barrier Fencing Sumatran Tiger
- d. Exclusion Fence Service Gate Detail
- e. Exclusion Fence & Swing Gate Detail
- f. Paddock Fencing Details

Receipt of the Addendum shall be acknowledged as part of your submission.


The Board of Management of the Toronto Zoo reserves the right to reject any or all Tenders or to accept any quotation, should it deem such action to be in its interests.


If you have any queries regarding this matter, please contact Mr. Peter Vasilopoulos, Supervisor, Purchasing & Supply, at 416-392-5916 or by email pvasilopoulos@torontozoo.ca.

Yours truly,


Peter Vasilopoulos Supervisor, Purchasing & Supply	
I/we hereby acknowledge receipt of this addendum and make allowance in my bid.	
Signed (Must be Signing Officer of Firm)	
Name of Firm	
Date:	
_	


END OF ADDENDUM 1








18' High Barrier Fence Section














NOTE: MESH AND HARDWARE TO BE GALVANIZED AND BLACK VINYL COATED POSTS AND RAILS TO BE GALVANIZED AND PAINTED BLACK

NOTES:

- ALL FENCE PIPE TO BE SCHEDULE 40.
- ALL FENCE COMPONENTS TO BE GALVANIZED STEEL.
- ALL FENCE HARDWARE TO BE INDUSTRIAL GRADE.
- ALL FENCE AND DOOR FRAMES MIN I", MAX 2" ABOVE GRADE.
- ALL SYSTEM FASTENERS, SUCH AS NUT SIDE OF BOLT, TO FACE AWAY FROM ANIMAL SIDE. WHERE ANIMALS ARE ON BOTH SIDES FASTENERS MUST BE WELDED. EXPOSED BOLT TIPS MUST BE TRIMMED TO \$ PROTRUSION.
- WELD ALL JOINTS, WIRE BRUSH/SAND BLAST WELDS AND COAT WITH ZING RICH PAINT.
- CHAINLINK MESH KNUCKLE-KNUCKLE
- ALL LINE AND TERMINAL POSTS SHALL BE SET IN CONCRETE FOOTINGS OF THE PROPER DIAMETER AND SHAPE TO ENSURE ADEQUATE SUPPORT. ALL FOOTINGS TO HAVE 6" OF \$" CLEAR DRAINAGE GRAVEL BELOW.